

Priority Areas Lead Testing and Corrective Actions June 2018
 Naval Construction Battalion Center Gulfport Child Development Center Building 31

Table 1. Summary of Results													
SAMPLING LOCATION DESCRIPTION				INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS		POST REMEDIATION SAMPLING RESULTS	
				CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured?			Recommended Level = 20ppb	
Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb)							Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)			
SAMPLING DATE				6/30/2018				mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy			mm/dd/yyyy
RESULTS DATE				7/26/2018				mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy			mm/dd/yyyy
DRINKING	GPT-31-HALL-WFC-A-FD - 1)	(BLDG 31 Fountain by lobby Cooler fountain	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GPT-31-HALL-WFC-B-FD - 2)	(BLDG 31 Fountain by lobby Cooler fountain	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
DRINKING	GPT-31-HALL-WFC-C-FD - 3)	(BLDG 31 Fountain by lobby Bottle filling station attached to Cooler fountain	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GPT-31-RM151-LOUNGE-K-FD (BLDG 31 - 18)	Teacher's Lounge Food prep sink	0.89	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GPT-31-RM113-K-KA-FD - 56)	(BLDG 31 Kitchen prep sink Food	4.10	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GPT-31-RM113-K-KB-FD - 57)	(BLDG 31 Kitchen prep sink Food	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
COOKING	GPT-31-RM113-K-KC-FD - 58)	(BLDG 31 Kitchen prep sink Food	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM158-RM-HHW-A-FD (BLDG 31 - 4)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM158-RM-HHW-B-FD (BLDG 31 - 5)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM157-RM-HHW-A-FD (BLDG 31 - 6)	Infant Room High hand wash sink	1.00	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM157-RM-HHW-B-FD (BLDG 31 - 7)	Infant Room High hand wash sink	0.82	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM156-RM-HHW-A-FD (BLDG 31 - 8)	Infant Room High hand wash sink	1.50	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM156-RM-HHW-B-FD (BLDG 31 - 9)	Infant Room High hand wash sink	2.00	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM155-RM-HHW-A-FD (BLDG 31 - 10)	Infant Room High hand wash sink	1.70	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM155-RM-HHW-B-FD (BLDG 31 - 11)	Infant Room High hand wash sink	1.40	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM154-RM-HHW-A-FD (BLDG 31 - 12)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions June 2018
 Naval Construction Battalion Center Gulfport Child Development Center Building 31

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	Recommended Level = 20ppb					
First Draw (ppb)	Retest required?	Date Fixture Secured?				Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	Description	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			6/30/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
RESULTS DATE			7/26/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
WASHING	GPT-31-RM154-RM-HHW-B-FD (BLDG 31 - 13)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM152-RM-HHW-A-FD (BLDG 31 - 14)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM152-RM-HHW-B-FD (BLDG 31 - 15)	Infant Room High hand wash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM123-BATH-HHW-A-FD (BLDG 256 - 16)	Women's Restroom High handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM123-BATH-HHW-B-FD (BLDG 256 - 17)	Women's Restroom High handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM147-RM-HHW-FD (BLDG 31 - 19)	Toddler Room High handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM147-RM-LHW-A-FD (BLDG 31 - 20)	Toddler Room Left low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM147-RM-LHW-B-FD (BLDG 31 - 21)	Toddler Room Right low handwash sink	1.90	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM145-RM-HHW-FD (BLDG 31 - 22)	Toddler Room High handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM145-RM-LHW-A-FD (BLDG 31 - 23)	Toddler Room Left low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM145-RM-LHW-B-FD (BLDG 31 - 24)	Toddler Room Right low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM143-RM-HHW-FD (BLDG 31 - 25)	Toddler Room High handwash sink	1.40	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM143-RM-LHW-A-FD (BLDG 31 - 26)	Toddler Room Left low handwash sink	1.10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM143-RM-LHW-B-FD (BLDG 31 - 27)	Toddler Room Right low handwash sink	1.80	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM141-RM-HHW-FD (BLDG 31 - 28)	Pre-Toddler Room High handwash sink	0.74	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM141-RM-LHW-A-FD (BLDG 31 - 29)	Pre-Toddler Room Left low handwash sink	1.70	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM141-RM-LHW-B-FD (BLDG 31 - 30)	Pre-Toddler Room Right low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions June 2018
 Naval Construction Battalion Center Gulfport Child Development Center Building 31

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			Recommended Level = 20ppb							Recommended Level = 20ppb	
CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured?	Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	Description	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			6/30/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
RESULTS DATE			7/26/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
WASHING	GPT-31-RM139-RM-HHW-FD (BLDG 31 - 31)	Pre-Toddler Room High handwash sink	0.79	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM139-RM-LHW-A-FD (BLDG 31 - 32)	Pre-Toddler Room Left low handwash sink	2.00	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM139-RM-LHW-B-FD (BLDG 31 - 33)	Pre-Toddler Room Right low handwash sink	0.90	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM135-RM-HHW-FD (BLDG 31 - 34)	Pre-Toddler Room High handwash sink	1.00	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM135-RM-LHW-A-FD (BLDG 31 - 35)	Pre-Toddler Room Left low handwash sink	1.00	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM136-RM-LHW-B-FD (BLDG 31 - 36)	Pre-Toddler Room Right low handwash sink	3.80	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM133-RM-HHW-FD (BLDG 31 - 37)	Pre-Toddler Room High handwash sink	1.20	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM133-RM-LHW-A-FD (BLDG 31 - 38)	Pre-Toddler Room Left low handwash sink	1.30	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM133-RM-LHW-B-FD (BLDG 31 - 39)	Pre-Toddler Room Right low handwash sink	4.00	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM131-RM-HHW-FD (BLDG 31 - 40)	Training Room High handwash sink	2.20	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM131-RM-LHW-A-FD (BLDG 31 - 41)	Training Room Left low handwash sink	5.90	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM131-RM-LHW-B-FD (BLDG 31 - 42)	Training Room Right low handwash sink	16.00	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM128-RM-HHW-FD (BLDG 31 - 43)	Toddler Room High handwash sink	1.30	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM128-RM-LHW-A-FD (BLDG 31 - 44)	Toddler Room Left low handwash sink	0.86	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM128-RM-LHW-B-FD (BLDG 31 - 45)	Toddler Room Right low handwash sink	1.10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM126-RM-HHW-FD (BLDG 31 - 46)	Toddler Room High handwash sink	1.50	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM126-RM-LHW-A-FD (BLDG 31 - 47)	Toddler Room Left low handwash sink	3.50	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions June 2018
 Naval Construction Battalion Center Gulfport Child Development Center Building 31

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
			CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured?		Recommended Level = 20ppb	
Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)							Description	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			6/30/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
RESULTS DATE			7/26/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
WASHING	GPT-31-RM126-RM-LHW-B-FD (BLDG 31 - 48)	Toddler Room Right low handwash sink	1.50	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM121-RM-HHW-FD (BLDG 31 - 49)	Training Room High handwash sink	3.20	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM121-RM-LHW-A-FD (BLDG 31 - 50)	Training Room Left low handwash sink	8.50	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM121-RM-LHW-B-FD (BLDG 31 - 51)	Training Room Right low handwash sink	2.10	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM118-RM-LHW-A-FD (BLDG 31 - 52)	Pre-School Room Left low handwash sink	1.20	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM118-RM-LHW-B-FD (BLDG 31 - 53)	Pre-School Room Right low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM116-RM-LHW-A-FD (BLDG 31 - 54)	Pre-School Room Left low handwash sink	2.50	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM116-RM-LHW-B-FD (BLDG 31 - 55)	Pre-School Room Right low handwash sink	0.98	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM113-K-HHW-FD (BLDG 31 - 59)	Kitchen Hand wash sink	3.30	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM111-RM-LHW-A-FD (BLDG 31 - 60)	Pre-School Room Left low handwash sink	non-detect	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM111-RM-LHW-B-FD (BLDG 31 - 61)	Pre-School Room Right low handwash sink	0.89	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM108-RM-LHW-A-FD (BLDG 31 - 62)	Pre-School Room Left low handwash sink	2.50	NO	N/A	N/A	N/A	N/A		N/A	N/A
WASHING	GPT-31-RM108-RM-LHW-B-FD (BLDG 31 - 63)	Pre-School Room Right low handwash sink	0.91	NO	N/A	N/A	N/A	N/A		N/A	N/A

Priority Areas Lead Testing and Corrective Actions June 2018
 Naval Construction Battalion Center Gulfport Child Development Center Building 31

SAMPLING LOCATION DESCRIPTION			INITIAL SAMPLING RESULTS			RE-SAMPLING RESULTS			CORRECTIVE ACTIONS	POST REMEDIATION SAMPLING RESULTS	
CATEGORY Water Intended For:	SAMPLE ID	Outlet Description	First Draw (ppb)	Retest required?	Date Fixture Secured?	Recommended Level = 20ppb				Description	Recommended Level = 20ppb
						Water Fountain 15 min. Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb)		Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)
SAMPLING DATE			6/30/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	
RESULTS DATE			7/26/2018			mm/dd/yyyy	mm/dd/yyyy	mm/dd/yyyy		mm/dd/yyyy	

Table 2. Summary Statistics

CATEGORY	INITIAL SAMPLING RESULTS	RE-SAMPLING RESULTS			POST REMEDIATION RESULTS
	Recommended Level = 20ppb				
	First Draw (ppb)	Water Fountain Follow up Flush Sample - Collected day before First Draw Sampling (ppb)	First Draw (ppb)	Follow up Flush - Collected 30 seconds after First Draw Sampling (ppb)	First Draw (ppb)
Total Drinking	3	0	0	0	0
Total Drinking > 20 ppb	0	0	0	0	0
Total Cook/Brush	4	0	0	0	0
Total Cook/Brush > 20 ppb	0	0	0	0	0
Total Washing	56	0	0	0	0
Total Washing > 20 ppb	0	0	0	0	0
Total Samples	63	0	0	0	0
Total Samples > 20 ppb	0	0	0	0	0